



TAMILNADU WATER SUPPLY AND DRAINAGE BOARD
DISTRICT WATER TESTING LABORATORY

No.15/20,38B/5A, Rajaji Nagar, College Road, Ariyalur-621704.

Phone: 04329 - 220142

E-mail: dwtlariyalur@gmail.com



TC - 10747

TEST REPORT

Doc.No: DWTL/FORM/7.8/01

Report No:	TR/2024/ 2057-1	Report Issue Date :	24.04.2024.	Page No : 01 of 01
Invoice Details:	1902/Dt.20.04.2024 Amt.Rs.1652/-	ULR No:	TC107472400000132F	

Client Name & Address Contact No / Email.ID		:	Sri Ramakrishna Public School, Venkatakrishnapuram, Ariyalur (Dt) (TK).			
Sample Name		:	Water			
Sample Number		:	2057-1			
Sample Description		:	Drinking water			
Sample Submitted by		:	Mr.Umashankar			
Location & Date		:	Sri Ramakrishna Public School, Venkatakrishnapuram & 20.04.2024			
Quantity of sample Received		:	2 Litre			
Sample Container		:	Jerry Cane			
Sample Condition on Receipt		:	Good			
Sample Received On		:	20/04/2024			
Test Commenced on		:	20/04/2024			
Test Completed on		:	24/04/2024			
Environmental Condition		:	26.0°C			
S.No	Parameters	Unit	Test Method	Result	Specification as per IS 10500:2012(RA:2019)	
					Acceptable Limit	Permissible Limit in the absence of alternate source
1	pH @ 25° C	-	IS 3025 Part 11-2022	7.28	6.5-8.5	6.5-8.5
2	Total Alkalinity as CaCO ₃	mg/L	IS 3025 Part 23-2023	480	200	600
3	Total Hardness as CaCO ₃	mg/L	IS 3025 Part 21-2009	356	200	600
4	Chloride as Cl	mg/L	IS 3025 Part 32-1988	272	250	1000
5	Sulphate as SO ₄	mg/L	IS 3025 Part 24-Section-1-2022	42.0	200	400
6	Nitrate as NO ₃	mg/L	APHA 23rd Edition 2017- 4500 -NO3 B	12.50	45	45
7	Fluoride as F	mg/L	APHA 23rd Edition 2017 - 4500- F-D	0.84	1.0	1.5

Remark: The tested sample conformed to IS: 10500:2012 (RA: 2019) Drinking water specification with respect to above tested parameters.
The Decision rule is not applicable.

.....End of the report.....

Verified by:

Note:

1. The test results relate only to the items tested.
2. The test report shall not be reproduced anywhere except in full and in the same format without the permission of the laboratory.
3. Unless informed by customer, the test items will not be retained for more than 15 days from the date of issue of the test report.
4. The result applied to the sample as received basis.

Authorised Signatory

S.SUGUNARAJ - Assistant Executive Engineer,
TWAD Board, Ariyalur.

**TAMILNADU WATER SUPPLY AND DRAINAGE BOARD****DISTRICT WATER TESTING LABORATORY**

No.15/20,38B/5A, Rajaji Nagar, College Road, Ariyalur-621704.

Phone: 04329 - 220142

E-mail: dwtlariyalur@gmail.com

TEST REPORT

Doc.No: DWTL/FORM/7.8/01

Report No:	TR/2024/ 2057-2	Report Issue Date :	24.04.2024	Page No:01 of 02
Invoice Details:	1902/Dt.20.04.2024/Amt.Rs.1652/-			

Client Name & Address	: Sri Ramakrishna Public School, Venkatakrishnapuram, Ariyalur (Dt) (TK).
Contact No / Email.ID	
Sample Name	: Water
Sample Number	: 2057-2
Sample Description	: Drinking water
Sample Submitted by	: Mr.Umashankar
Location & Date	: Sri Ramakrishna Public School, Venkatakrishnapuram & 20.04.2024
Quantity of sample Received	: 2 Litre
Sample Container	: Jerry Can
Sample Condition on Receipt	: Good
Sample Received On	: 20/04/2024
Test Commenced on	: 20/04/2024
Test Completed on	: 24/04/2024
Environmental Condition	: 26.0°C

S.No	Parameters	Test Method	Unit	Result	Specification as per IS 10500 : 2012	
					Acceptable Limit	Permissible Limit in the absence of alternate source
1	Appearance	Visual observation	--	Clear	Clear	Clear
2	Odour	IS 3025 Part 5 : 1983	--	Agreeable	Agreeable	Agreeable
3	Turbidity	APHA 23rd Edition 2017 - 2130 B	NTU	1	1	5
4	Total Dissolved Solids	APHA 23rd Edition 2017 - 2540 C	mg/L	1322	500	2000
5	Conductivity	APHA 23rd Edition 2017 - 2510 B	µS/cm	1889	-	-
6	P - Alkalinity	IS 3025-Part 23-1983	mg/L	0	-	-
7	Calcium as Ca	APHA 23rd Edition 2017 - 3500 Ca B	mg/L	79.2	75	200
8	Magnesium as Mg	APHA 23rd Edition 2017- 3500 Mg B	mg/L	37.9	30	100
9	Iron as Fe	APHA 23rd Edition 2017- 3500 Fe B	mg/L	0.0	0.3	1

Verified by:

Authorised Signatory
S.SUGUNARAJ - Assistant Executive Engineer,
TWAD Board, Ariyalur.

Note:

1. The test results relate only to the items tested.
2. The test report shall not be reproduced anywhere except in full and in the same format without the permission of the laboratory.
3. Unless informed by customer, the test items will not be retained for more than 15 days from the date of issue of the test report.
4. The result applied to the sample as received basis.



TAMILNADU WATER SUPPLY AND DRAINAGE BOARD

DISTRICT WATER TESTING LABORATORY

No.15/20,38B/5A, Rajaji Nagar, College Road, Ariyalur-621704.

Phone: 04329 - 220142

E-mail: dwtlariyalur@gmail.com

TEST REPORT

Doc.No: DWTL/FORM/7.8/01

Report No:	TR/2024/ 2057-2	Report Issue Date :	24.04.2024	Page No:02 of 02
Invoice Details:	1902/Dt.20.04.2024/Amt.Rs.1652/-			

S.No	Parameters	Test Method	Unit	Result	Specification as per IS 10500 : 2012	
					Acceptable Limit	Permissible Limit in the absence of alternate source
10	Manganese as Mn	APHA 23rd Edition 2017 – 3500 Mn B	mg/L	0	0.1	0.3
11	Ammonia as NH ₃	APHA 17th Edition-1989– 4500 NH3C	mg/L	0.00	0.5	0.5
12	Nitrite as NO ₂	APHA 23rd Edition 2017– 4500-NO2 B	mg/L	0.00	-	-
13	Total Phosphate as PO ₄	APHA 23rd Edition 2017 – 4500 P- D	mg/L	0.00	-	-
14	Tidys 4 hr. test	APHA 23rd Edition 2017 – 4500 O - B	mg/L	0.00	-	-
15	Residual Chlorine	IS/APHA	mg/L	0	0.2	1.0
BACTERIOLOGICAL EXAMINATION						
16	Fecal Coliform	IS/APHA	CFU/ 100ML	0	0	0

Report: The tested sample conformed to IS:10500:2012(RA: 2019)drinking water specification with respect to above tested parameters.

Report:- 2057- The water is Physically and Chemically Potable.
The water is Bacteriologically Not Contaminated.

.....End of the report.....

Verified by:

Authorised Signatory
S.SUGUNARAJ - Assistant Executive Engineer,
TWAD Board, Ariyalur.

Note:

1. The test results relate only to the items tested.
2. The test report shall not be reproduced anywhere except in full and in the same format without the permission of the laboratory.
3. Unless informed by customer, the test items will not be retained for more than 15 days from the date of issue of the test report.
4. The result applied to the sample as received basis.